

# McDonalds Restaurant

Media, PA



**Project Description:** During the geotechnical investigation, Whitestone Associates discovered 8-10' of fill on this site. After a review of the options, Whitestone recommended Geopier elements to control the settlement on this site. The Geopier installation crew arrived on site and installed the Geopier elements in just 2 ½ days. This allowed the concrete footings to be placed promptly and construction to move ahead on schedule.

## THE GEOPIER ADVANTAGE

- Fast installation – Geopier elements were installed in 2½ days
- Fixed price for Geopier system – unlike other deep foundations
- Geopier elements saved time and money over the other deep foundation systems considered for this project.

**Owner:** McDonalds Corporation, Plymouth Meeting, PA

**Architect:** McDonalds Corporation

**Structural Engineer:** Bohler Engineering, Inc., North Wales, PA

**Geotechnical Engineer:** Whitestone Associates, Inc., Watchung, NJ